




PURCHASE ORDER Philhealth Regional Office 02					
Supplier: MASANGKAY COMPUTER CENTER Address: 1143 G. Masangkay Street, Sta Cruz, Manila TIN: _____ Mode of Procurement: Public Bidding			PO NO. : 16-04-0025 Date : April 25, 2016 P. R. NO: _____ Date : _____		
<p>Gentlemen:</p> <p>Please furnish this office the following articles subject to the terms and conditions contained herein.</p>					
Place of Delivery: The Builder's Place, Del Rosario St., Tug. City Date of Delivery: _____			Delivery Term: 25 days (8:00AM to 5:PM) Payment Term: Credit		
Stock #	Unit	Description	Qty.	Unit Cost	Amount
	sets	BRAND NEW GENERATOR SETS – Laidong/Extreme	2	718,900.00	1,437,800.00
		Standby Capacity : 16 KVA			
		Power Output : Alternating Current			
		Voltage/Phase/RPM : 220V/Single phase/1800			
		Type : Enclosed canopy, Silent/Low Noise			
		Engine : Diesel Internal Combustion Engine			
		Generator : Synchronous			
		Features:			
		1. Control panel in NEMA 12 type metal enclosure with electronic monitoring window showing accurate readings of Voltage, Amperage, Frequency, RPM, Engine water temperature, Oil pressure, fuel level and other pertinent readings.			
		2. Capable of maintaining set frequency even at higher load.			
		3. Ability to keep engine battery on charge when not in used.			
		4. Molded case circuit breaker with thermal magnetic trip. Circuit breaker should be mounted in a NEMA 12 type metal enclosure.			
		5. Instrumentation and electrical controls conform to NEMA ICS 1 standard as capable.			
		6. With steel mounting, vibration absorbers, engine & generator supports and other standard safety features.			
		INSTALLATION:			
		1. Layout and install 22 mm ² THHN cable inside 32mm dia. IMC conduit from MDP & MTS to Generator set.			
		2. Provide and install a Manual Transfer Switch (MTS) with 100A circuit breakers. Circuit breakers to be used should be commercial/industrial molded case type with thermal magnetic trip.			
		3. Layout electrical conduits in a proper alignment and provide sufficient steel clamps or steel brackets with equal distances.			
		4. Provide extended exhaust pipe at a minimum length of 2m.			
		5. If required, provide necessary housing with roofing if the generator set will be installed outside the office building. Submit shop drawing of housing for approval prior to construction.			
		TESTING & COMMISSIONING:			
		1. The generator set should be tested by operating it continuously at a minimum of 4 hours but not to exceed 8 hours.			
		a. 1 st Hour 25% load			
		b. 2 nd Hour 50% load			
		c. 3 rd Hour onwards 100% load			

	2. If ever the generator set failed during the testing period due to some minor fault/s, testing has to be repeated starting from the 1 st hour.			
	3. Provide supply of Diesel fuel to the generator set for the entire duration of testing.			
	4. Testing & commissioning shall be conducted by supplier's technical representatives and must be witnessed by PHIC authorized representatives.			
	5. During the testing & commissioning, the necessary readings for the required recordings should be within the standard parameters, if not, PHIC authorized representatives may stop the testing and declare it as failed. Also, the PHIC authorized representatives have the right to terminate the testing if they find error/s or malfunctioning/s in the generator set.			
	NOTE: The above specifications are not tailor-fitted to any particular brand. Warranty: Two (2) years warranty based from date of delivery and commissioning under normal use and operation for standby application of 1500 running hours, whichever comes first.			
(Total Amount in Words)				
<p>In case of failure to make the full delivery within the time specified above, a penalty of one-tenth (1/10) of one percent for every day of delay shall be imposed. Render your bills in triplicate copies including the original. If the date of receipt of the PO by the dealer is not indicated, it shall be deemed received on the 10th working day from the date of the approval of the PO. For imported items, IMPORTANT DOCUMENTS specifically showing the condition, serial numbers of the equipment purchased and the tax receipts should be submitted by the supplier.</p>				
CONFORME:		Very truly yours,  LOVELYN B. SABBAN Division chief IV		
(Signature over Printed Name of Supplier)				
APPROVED BY:  OSCAR B. ABADU, JR. Regional Vice President				
Funds Available:		OBJECT OF EXPENDITURES AMOUNT		
 KEILLY MAE D. CALIMAG Fiscal Controller IV		1. _____ 2. _____ 3. _____		